

**Louisville High School Addition and Renovations**  
**Louisville City School District**  
**Louisville, OH**  
**Project No. 207145.02**  
**OSFC Grant No. 362**

**PROJECT OVERVIEW**

Louisville High School will undergo various renovations to its 145,106 SF of existing building area, as well as receive a modest addition of approximately 14,586 square feet.

The additions are currently being designed, and are slated to include a new auditoria, stage, food service operations, public restrooms, building administration spaces and secure vestibule with connecting corridor, as well as associated support spaces. The finishes in the addition will compliment and be consistent with those found in the existing facility after renovations have been completed.

This project is being co-funded by the local Louisville community as well as the Ohio School Facilities Commission (OSFC). Once complete, this facility is slated to house approximately 962 students in grades 9-12, under approximately 159,692 SF of building area.

**PROJECT DESCRIPTION**

Louisville High School will undergo various renovations to its 145,106 SF of existing building area, as well as receive a modest addition of approximately 14,586 square feet.

The additions are currently being designed, and are slated to include a new auditoria, stage, food service operations, public restrooms, building administration spaces and secure vestibule with connecting corridor, as well as associated support spaces. The finishes in the addition will compliment and be consistent with those found in the existing facility after renovations have been completed.

This project is being co-funded by the local Louisville community as well as the Ohio School Facilities Commission (OSFC). Once complete, this facility is slated to house approximately 962 students in grades 9-12, under approximately 159,692 SF of building area.

Renovations to the three building areas (1967 original building, 1974 addition, and 2004 addition) of the existing facility are slated to address all major systems throughout the building, as needed. Most, if not all, systems in the 2004 building area will remain untouched. Work in the 1967 and 1974 building areas will include complete replacement of the HVAC systems, roofing systems, electrical systems, toilets and flush valves, window systems, general finishes, interior lighting systems, emergency egress lighting systems, fire alarm system, accessibility systems, exterior entry systems, and life safety systems. Miscellaneous foundation work, exterior masonry work, security systems, exterior lighting, as well as rework of site circulation will also be incorporated into the project design. The remaining identified hazardous materials will be abated to provide a school environment completely free of identified hazardous materials. Technology wiring and infrastructure will be replaced as needed throughout the building, as well as worn, outdated or inadequate furniture. Once complete, the building should serve the students attending Louisville High School for many years to come and be on par with other new and renovated facilities across the state of Ohio.